



Report No: URPT-20260917-0004

Certificate No: N/A

Date: 17-09-2026

TEST REPORT
California Bearing Ratio
Retest — Execution #17 (Previous: #10138)

Report No: URPT-20260917-0004
Execution: #17 | Result Rev: 2 | Report Rev: 1
Sample: TX-B5-SOIL-001 | Case: DMSPL-B5-001

Overall Decision: FAIL
Approved: 17 Sep 2026 19:25
Tested: 17 Sep 2026 17:10

Customer / Sample

CustomerDhruv

AddressSouth Bopal, Ahmedabad, 380058

SampleTX-B5-SOIL-001 — Subgrade Soil Sample KM 42+500

GradeSUBGRADE

Branch / DeptDevine Laboratory / Geotechnical / Soil Department

Received16 Sep 2026

Test & Method (frozen)

TestSOIL_CBR — California Bearing Ratio

Discipline-

MethodCalifornia Bearing Ratio

Method Version1987

SpecificationPROJECT_SUBGRADE_CBR_SPEC - Project Subgrade CBR Specification

LayoutSOIL_CBR_LAYOUT (ObservationMatrix)

Results (finalized values)

Parameter	Result	Unit	Min	Max	Verdict
MOISTURE_CONTENT — Moisture Content	12.50	%	8.000000	12.000000	FAIL
DRY_DENSITY — Dry Density	1.80	g/cc	1.700000	2.000000	PASS
MAX_DRY_DENSITY — Maximum Dry Density	2.00	g/cc	1.600000	2.400000	PASS
COMPACTION — Compaction	90.00	%	95.000000	100.000000	FAIL
SAMPLE_PREPARATION_MOISTURE — Preparation Moisture	11.00	%	8.000000	14.000000	PASS
SURCHARGE_LOAD — Surcharge Load	5.00	kg	4.000000	6.000000	PASS
PENETRATION_2_5MM_LOAD — Load at 2.5 mm Penetration	6.60	kN	0.500000	2.000000	FAIL
PENETRATION_5_0MM_LOAD — Load at 5.0 mm Penetration	9.90	kN	0.800000	2.500000	FAIL
CBR_2_5 — CBR at 2.5 mm	50.00	%	5.000000	15.000000	FAIL
CBR_5_0 — CBR at 5.0 mm	50.00	%	5.000000	15.000000	FAIL
CBR_RESULT — CBR Result	50.00	%	6.000000	100.000000	PASS

Decision: ALL_REQUIRED_PASS | Acceptance: -

Conditions (configured vs actual)

Condition	Configured	Actual
- — Curing Age	= - -	-
- — Moisture Condition	= - -	-
- — Specimen Thickness	= - mm	-

Equipment (requirement vs used)

Equipment	Requirement	Calibration
Casagrande Apparatus	-	- (valid upto -)

Measurement Uncertainty (frozen)

Type: Expanded Uncertainty (k=2) | U = 2.500000 % (k = 2.0000, basis Type B)

Review / Verification / Approval

AnalystSystem Admin

ReviewerSystem Admin

Verified BySuper Admin 17 Sep 2026 19:25

Approved BySudhanshu Singh 17 Sep 2026 19:25

Review RemarksR8-05 verified



DIVINE METALLURGICAL SERVICES PVT. LTD.

14, Gopal Industrial Estate, Vallabh Nagar, BRTS, Odhav, Ahmedabad - 382415

Report No: URPT-20260917-0004

Certificate No: N/A

Date: 17-09-2026

Approval Remarks

R8-08 approved

Findings: 2 total, 1 open

Recorded scope status: Referenced; accreditation mark applied only where WithinScope.

System Admin

Super Admin

Sudhanshu Singh